



## Resumo

Materal	Qtd	Rendimento	Consumo água	Consumo Total
Concreto	14.974,70 m <sup>3</sup>	-	180 l/m <sup>3</sup>	2.695.446,00 L
Argamassa Reboco	145.337,21 m <sup>2</sup>	0,025 m <sup>3</sup> /m <sup>2</sup>	210 l/m <sup>3</sup>	763.020,36 L
Argamassa Assentamento Alvenaria	64.833,31 m <sup>2</sup>	0,0378 m <sup>3</sup> /m <sup>2</sup>	210 l/m <sup>3</sup>	514.646,78 L
Argamassa Contrapiso	70.929,83 m <sup>2</sup>	0,05 m <sup>3</sup> /m <sup>2</sup>	180 l/m <sup>3</sup>	638.368,44 L
Argamassa Assentamento Revestimento Ceramico	43.456,43 m <sup>2</sup>	10 kg/m <sup>2</sup>	0,135 l/kg	58.667,18 L
Tintas	253.102,38 m <sup>2</sup>	0,3l/m <sup>2</sup>	0,2l/l	15.186,14 L
Argamassa Assentamento Granito	7.271,51 m <sup>2</sup>	10 kg/m <sup>2</sup>	0,135 l/kg	9.816,53 L
Forro Gesso	56.920,94 m <sup>2</sup>	-	2 l/m <sup>2</sup>	113.841,88 L
Limpeza Pós Obra	56.396,00 m <sup>2</sup>	-	0,25 l/m <sup>2</sup>	14.099,00 L
Limpeza Ferramentas / Consumo Canteiro	1.460,00 dias	-	200 l/dia	292.000,00 L
				<b>5.115.092,30 L</b>